BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Name Of Work :- Operation and Maintenance of Street Lighting System in Ward No.09 Package Y-9 of Yelahanka Zone.

Sl. No	Qty	Description Of Work	Unit	Approved Rates	
				In figures	In words
1	382	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. i) Poles with 36/40 W fluorescent tube light street lighting system.	Each	515.00	Rupees Five Hundred Fifteen Only
2	320	Poles with 125 W MV light Park lighting system.	Each	570.00	Rupees Five Hundred Seventy Only
3	3022	Poles with 250W HPSV light street lighting system.	Each	1033.00	Rupees One Thousand Thirty Three Only
4	148	Poles with 400 watts HPSV light street lighting system.	Each	840.00	Rupees Eight Hundred Forty Only
5	25	Poles with 24 W LED light street lighting system.	Each	1100.00	Rupees One Thousand One Hundred Only
6	190	Poles with 65 W LED light street lighting system.	Each	1434.00	Rupees One Thousand Four Hundred Thirty Four Only
7	20	Poles with 90 W LED light street lighting system.	Each	1722.00	Rupees One Thousand Seven Hundred Twenty Two Only
8	21	Operation and maintenance of Manual and Automatic Timer Switching circuits including replacement of electrical gadgets, such as MCB's Contactors, Timer, Cut-outs, wiring connector and M.S. Box with proper insulation etc., complete.	Each	2340.00	Rupees Two Thousand Three Hundred Forty Only
9	320	B Work to be carried out as per requirement & actuals and as per the direction of the in charge engineer, Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/looting of the pole a)5 mtr pole	Each	687.00	Rupees Six Hundred Eighty Seven Only
10	56	c) 8 Mtr and above street light pole	Each	962.00	Rupees Nine Hundred Sixty Two Only
11	13	Moulded Case Circuit Breaker (MCCB) Three Pole 100Amps 25kA	Each	3395.00	Rupees Three Thousand Three Hundred Ninety Five Only

For, Entire Enterprises

Proprietor

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
[illegible]ataraynapura, Bangalore-92

12	13	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200mmx200mmx98mm	Each	2720.00	Rupees Two Thousand Seven Hundred Twenty Only

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For, Entire Enterprises

Proprietor

Contractor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone